

1 COPY OF TEST REPORTS SHOWING THE RESULTS OF HYDROSTATIC TEST IS REQUIRED.

THE PART SHALL REQUIRE A HYDROSTATIC TEST AT 1.5 TIMES THE DESIGN OR WORKING PRESSURE AS SPECIFIED IN THE FABRICATION DOCUMENT FOR A MINIMUM DURATION OF 30 MINUTES PLUS SUFFICIENT TIME TO ACCOUNT FOR INSPECTION. NO WEEPAGE IS ALLOWED.

TEST REPORTS AND/OR OTHER VERIFICATION OF CONFORMANCE DOCUMENTS SHALL BE SIGNED AND DATED BY THE SELLER'S AUTHORIZED REPRESENTATIVE AND MUST INDICATE THE SPECIFICATION/DRAWING REVISION TO WHICH THE SPECIFIED TEST WAS PERFORMED.

EVIDENCE OF ALL TESTS AND INSPECTIONS PERFORMED AS REQUIRED BY THE SPECIFICATIONS MUST BE MAINTAINED BY THE SELLER. HOWEVER, RECORDS FOR ONLY THOSE TESTS REQUESTED ABOVE SHALL BE FORWARDED WITH THE SHIPMENT.

TEST REPORTS SHALL BE ATTACHED TO THE PACKING LIST. WHERE MORE THAN ONE CONTAINER OR PACKAGE IS INCLUDED IN THE SHIPMENT, THE TEST REPORTS SHALL BE ATTACHED SECURELY TO OR PLACED IN ONE CONTAINER OR PACKAGE AND CLEARLY IDENTIFIED ON THE OUTSIDE.