

Mid-position the valve stem / disc prior to welding. If the valve stem / disc cannot be placed in mid-position, the valve shall be disassembled prior to welding. Swing check and lift check valves can be mid-positioned by turning the valve upside down prior to welding.